

GROND ONTGRAVEN TEN BEHOEVE VAN WATERGANG

Omschrijving

Omschrijving

Grond ontgraven ten behoeve van watergang.
Taluds van 1:1 tot 1:3.

Tabel

	Hoeveelheid uitkomend materiaal in m ³ /m	Bodembreedte watergang in m	Hoeveelheid uit te graven m ³	Ontgraven en terzijde zetten
Kosten per m ³	Tot 1	Tot 2	50	1.00
			100	0.91
			500	0.83
			1.000	0.79
		2 - 4	50	1.11
			100	1.01
			500	0.92
			1.000	0.88
		4 - 8	50	2.31
			100	2.21
			500	2.10
			1.000	2.00
	1 - 3	Tot 2	50	0.77
			100	0.70
			500	0.64
			1.000	0.61
		2 - 4	50	0.86
			100	0.78
			500	0.71
			1.000	0.67
		4 - 8	50	1.78
			100	1.69
			500	1.62
			1.000	1.54
	3 - 10	Tot 2	50	0.67
			100	0.61
			500	0.55
			1.000	0.53
		2 - 4	50	0.74
			100	0.68

			500	0.62
			1.000	0.59
	4 - 8		50	1.55
			100	1.47
			500	1.41
			1.000	1.34

Uur per m ³	Tot 1	Tot 2	50	0,013
			100	0,012
			500	0,011
			1.000	0,010
	2 - 4		50	0,015
			100	0,013
			500	0,012
			1.000	0,011
	4 - 8		50	0,029
			100	0,028
			500	0,026
			1.000	0,025
	1 - 3	Tot 2	50	0,010
			100	0,009
			500	0,008
			1.000	0,008
	2 - 4		50	0,011
			100	0,010
			500	0,009
			1.000	0,009
	4 - 8		50	0,022
			100	0,021
			500	0,020
			1.000	0,019
	3 - 10	Tot 2	50	0,009
			100	0,008
			500	0,007
			1.000	0,007
	2 - 4		50	0,010
			100	0,009
			500	0,008
			1.000	0,008
	4 - 8		50	0,020
			100	0,019
			500	0,018
			1.000	0,017

m ³ per uur	Tot 1	Tot 2	50	76,250
			100	83,875
			500	92,250
			1.000	96,875

1 - 3	2 - 4	50	68,625
		100	75,500
		500	83,000
		1.000	87,250
	4 - 8	50	34,375
		100	36,000
		500	37,875
		1.000	39,750
	Tot 2	50	99,125
		100	109,000
		500	120,000
		1.000	126,000
	2 - 4	50	89,250
		100	98,125
		500	108,000
		1.000	113,375
3 - 10	4 - 8	50	44,625
		100	46,875
		500	49,125
		1.000	51,625
	Tot 2	50	114,000
		100	125,375
		500	137,875
		1.000	144,875
	2 - 4	50	102,625
		100	112,875
		500	124,125
		1.000	130,375
	4 - 8	50	51,250
		100	53,875
		500	56,500
		1.000	59,375